BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Drilling of Borewell, Providing and Installing Pump, Motor and other accessories in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	5	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2	250.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
	250.00	50 to 100 m	Rmtr	412.00	Rupees Four Hundred Twelve Only
	250.00	100 to 150 m	Rmtr	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
	250.00	150 to 200 m	Rmtr	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
	250.00	200 to 250 m	Rmtr	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
	250.00	250 to 300 m	Rmtr	600.49	Rupees Six Hundred and Forty Nine Paise Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
3	350.00	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
4	2700.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of **GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 4 Sqm mm** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	126.70	Rupees One Hundred Twenty Six and Seventy Paise Only
5	225	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	Per Length	88.00	Rupees Eighty Eight Only
6	5	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	302.00	Rupees Three Hundred Two Only
7	150.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	140.40	Rupees One Hundred Forty and Forty Paise Only
8	150.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. **P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm)** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.80	Rupees Ten and Eighty Paise Only
9	125.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	85.00	Rupees Eighty Five Only
10	20.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	345.00	Rupees Three Hundred Forty Five Only
11	5.00	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	280.00	Rupees Two Hundred Eighty Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
12	5	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, etc., complete and as per the directions of the Engineer-in-charge of the work	No	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
13	30	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	180.00	Rupees One Hundred Eighty Only
14	5	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. **5-32Amps Group A TPN** etc., complete and as per the directions of the Engineer-in-charge of the work	No	1547.00	Rupees One Thousand Five Hundred Forty Seven Only
15	117000.00	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.33	and Thirty Three Paise Only
16	843.75	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	188.00	Rupees One Hundred Eighty Eight Only
17	1875.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	123.00	Rupees One Hundred Twenty Three Only
18	843.75	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	61.00	Rupees Sixty One Only
19	90.00	Code No.: 3008 Providing 250mm dia PVC Pipe 10kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	2203.39	Rupees Two Thousand Two Hundred Three and Thirty Nine Paise Only
20	5	Providing and fixing Borewell Cap and Clamp Set etc., complete and as per the directions of the Engineer-in-charge of the work	Set	1800.00	Rupees One Thousand Eight Hundred Only

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
21	5	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps etc., complete and as per the directions of the Engineer-in-charge of the work	No	56414.00	Rupees Fifty Six Thousand Four Hundred Fourteen Only
22	1300.00	Providing GI Pipe 50 mm 'B' Class etc., complete and as per the directions of the Engineer-in-charge of the work	m	415.00	Rupees Four Hundred Fifteen Only
23	220	Providing Collar 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	No	180.00	Rupees One Hundred Eighty Only
24	5	Providing and fixing 50mm nominal bore gun metal non-return etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1800.00	Rupees One Thousand Eight Hundred Only
25	5	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.- **for 50mm dia**: etc., complete and as per the directions of the Engineer-in-charge of the work	Each	222.60	Rupees Two Hundred Twenty Two and Sixty Paise Only
26	5	Providing outdoor panel upto **15.00 HP** etc., complete and as per the directions of the Engineer-in-charge of the work	No.	15500.00	Rupees Fifteen Thousand Five Hundred Only
27	25	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **65mm nominal bore** including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Each	2229.18	Rupees Two Thousand Two Hundred Twenty Nine and Eighteen Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"No CORRECTIONS NIL"
"DTS APPROVED"
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ